BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Yelahanka Division
B.B.M.P. Bangalore - 64

APPROVED SCHEDULE - B

Name of work: Construction of culverts and improvements of drains at vinayaka layout in ward No 02 of yelahanka Sub Division.

Sl. No.	Description	Unit	Approved Quantity	Approved Rate Technical Manager, (west) KRIDL BBMP.	
				In Figures	In Words
1	Removing B.S. slab of Drain and stacking	sqm	459.00	65.72	Rupees seixty five and paise seventy
2	KSRRB 300 - Excavation for road, drains and similar works - KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH Chapte	Cum	140.04	86.92	Rupees Eighty six and paise ninty two only
3	KSRB 100-1 Loading and unloading ofstone aggregates / sand/ kanker/ Moorum /soil KSRRB M100-1 Placing tipper at loading with front end loader dumpting turning for return trip excluding time for haulged and return trip complete as per specification item No 17.1 page 130 and KSRB M.100.4.1 costof haulage excluding loading and unloading MORTH to a distance of 4.00 K.M	Cum	140.04	100.00	Rupees one hundred and paise zero only
4	Refixing stone slabs of drains and pointing in C M	sqm	413.10	80.56	Rupees eighty and paise fifty six only
5	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete 7.5 cms thick	sqm	234.90	665.68	Rupees six hundred sixty five and paise sixty eight only
6	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 withOPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS	Cum	37.80	5159.02	Rupees five thousand one hundred fifty nine and paise two only
7	KSRB 5-11 : Providing and constructing load bearing wall with cement concrete cavities blocks (hollow blocks) of proportion 1:1.5:3 blocks of size 40x20x20cms.(lxbxh) strength not less than 3.5 Newton per sqmm with cement mortar 1:4 conforming to I.S.2185 of 1967 having not less than 40mm.shell thickness with two or more large cavities and having solid material between including cost of materials, labour charges, scaffoldings, curing complete as per specifications.	sqm	380.80	974.14	Rupees nine hundred seventy four and paise fourteen only
8	KSRB 15.1.1: Providing flush pointing to square rubble, course or uncoursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications	sqm	380.80	102.82	Rupees one hundred two and paise Eighty two only

Sl. No.	Description	Unit	Approved Quantity	Approved Rate Technical Manager, (west) KRIDL BBMP.	
				In Figures	In Words
9	KSRB 4-1.7 : Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs with 20mm and down size graded granite metal coarse aggregate @ 0.84cum and fine aggregate @ 0.56 cum machine mixed concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications, specification. No	Cum	22.16	5598.92	Rupees Fifty nine thousand four hundred thirteen and paise zero only
10	Providing and fixing RCC precast Slabs of 0.10 m thick of CC 1:2:4 with 20 mm and down size graded granite metal , machine mixed , including cost of all material , labour , HOM of Machinery , curing complete	sqm	406.80	2100.00	Rupees two thousand one hundred and paise zero only
11	5.29(b)Providing and fixing pre cast solid cement concrete kerb stones made out of No.272.21 C.C 1:2:4 with top and bottom width 114 and 165mm repectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, including formwork curing, including, cost of all materials, labour hire charges of machinery, loading unloading, lead and lift, transportation etc, complete	No	1330.00	331.78	Rupees three hundred ten and pais fifty eight only
12	KSRB 15-19.2 :Providing and applying ready mix priming coat over concrete/masonry/asbestos cement sheet/plastered surfaces including preparing the surface after throughly cleaning of oil,grease,dirt and other foreign matter and sand papering including cost of materials, labour, complete as per specifications.	sqm	243.80	27.56	Rupees twenty seven and paise fifty six only
13	KSRB 800-1.Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications.	sqm	243.80	63.60	Rupees Sixty three and paise sixty only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer
Yelahanka Division
BBMP, Bangalore - 64